

EVP Control Mo	EVP Control Module terminal voltage table (reference)	
Terminal	Test condition or measured terminal	Specification (Reference)
Α	Under any condition	B+
C	EVP control unit terminal C—electric vacuum pump terminal B	Continuity detected
Е	EVP control unit terminal E—electric vacuum pump terminal A	Continuity detected
G	EVP control unit terminal G—ground point	Continuity detected
ם	Ignition off	1.0 V or less
-	Ignition ON (engine off)	B+
Y	EVP control unit terminal Y—vacuum sensor 1 terminal B	Continuity detected
Z	Because this terminal is for communication, determination using terminal voltage inspection is not possible. Perform the inspection using the DTC inspection.	
AA	EVP control unit terminal Y—vacuum sensor 1 terminal A	Continuity detected
AC	EVP control unit terminal Y—vacuum sensor 1 terminal C	Continuity detected
AD	Because this terminal is for communication, determination using terminal voltage inspection is not possible. Perform the inspection using the DTC inspection.	

